



October 2, 2015

Please acknowledge receipt of Addendum No. 1 enclosed, dated October 2, 2015, to the Project Plans and Specifications for the **GREYSTONE JOINT SEALANT AND VALVE COATINGS REHABILITATION** within the City of Beverly Hills, by signing and faxing a copy of this page upon receipt of this notification to our office at (310) 278-1838 or by emailing a scanned copy to tmalabanan@beverlyhills.org.

Please include the original copy with your proposal form for bid submittal on Thursday, October 15, 2015.

Sincerely,

T D Malabanan

Tristan D. Malabanan, P.E.
Civil Engineer

Receipt Acknowledged:

CONTRACTOR: _____

BY: _____

DATE: _____

ADDENDUM NO. 1

October 2, 2015

For the Construction of

GREYSTONE JOINT SEALANT AND VALVE COATINGS REHABILITATION

Within the City of

BEVERLY HILLS, CALIFORNIA

00000

ITEM 1 - On page N-5, delete the fourth paragraph starting with “*In submitting its bid, each Bidder will require...*”, and replace it with the following:

In submitting its bid, **each bidder** will be required to certify that he/she or their subcontractor(s) has a **minimum of three consecutive years** of current experience in the field of concrete repair and protection, confined space, coatings, reservoir rehabilitation, etc. similar to the scope of this project. In addition, each Bidder or their subcontractor(s) must have completed a reservoir construction, rehabilitation, or upgrade project within the past ten years. Contractor shall maintain qualified personnel who have received product training by a Sika representative. **If a Bidder fails to meet these qualifications, City shall consider the Bidder to be not responsible.**

ITEM 2 - On page 2-3, in Section 2-03.1 Special Work Requirements, add the following paragraphs:

n. Construction yard – the contractor may set up yard directly to the west of the reservoir entrance building. The yard may be used to store equipment and tools. The fencing with green privacy screen is required and must be well maintained. A high quality project sign shall be installed as well. The actual layout and size of the yard will be coordinated with City Staff after the contract is awarded.

m. The contractor must completely demobilize by April 27, 2016. All tools, equipment, fencing, etc. must be removed and the area must be cleaned and restored to preconstruction condition. The contractor shall remobilize after May 2, 2016.

ITEM 3 - On page 2-9, in Section 2-12.4 Item 4 & 14, delete the paragraph starting with “*i. The approximate amount of sealant...*”, and replace it with the following paragraph:

- i. The approximate amount of sealant is 3,716 LF for the west tank and 3,281 LF for the east tank. These amounts are based on the as-built drawings and include a 10% contingency amount.

ITEM 4 - On page 2-12, in Section 2-12.10 Item 10 & 20, delete the paragraph starting with “*c. Disinfection shall be in accordance with...*”, and replace it with the following paragraph:

- c. Disinfection shall be in accordance with AWWA C652-02 and any applicable standards. Use method 2 for disinfection. The tank shall be filled to capacity for testing. After the tank has been full for 5 days, VOC's and Bac-T testing will commence with rush analysis from the laboratory.